


TRACT 4

DESCRIPTION OF 0.9319 ACRES


Situated in Section 34, Town 5, Range 13, Canaan Township, Athens County Ohio and being more particularly described as follows:

Commencing at the northeast corner of said Section 34, thence north $85^{\circ} 00'$ west 1752.3 feet; thence south $5^{\circ} 00'$ west 1589.3 feet to an iron pin found; thence south $7^{\circ} 06' 12''$ west 228.18 feet to a stone found; thence north $82^{\circ} 45' 08''$ west 67.32 feet to a stone found; thence south $7^{\circ} 09' 24''$ west 355.93 feet to an iron pin found on the north line of Cook Drive, passing an iron pin set at 208.93 feet, said iron pin found being the point of beginning of the tract herein described; thence along the north line of Cook Drive south $78^{\circ} 32' 57''$ east 230.22 feet to an iron pin found, passing an iron pins set at 110.00 feet and 210.00 feet; thence south $7^{\circ} 14' 03''$ west 184.58 feet to an iron pin set on the north right of way line of East State Street; thence along the north line of East ^{state} Street north $74^{\circ} 45'$ west 231.63 feet to an iron pin set; thence leaving the right of way line north $7^{\circ} 09' 24''$ east 169.21 feet to the point of beginning and containing 0.9319 acres. .8042 acres being in the Second tract and .1277 acres being in the Third tract of the Deed Recorded in Volume 324, Page 607, Athens County Deed Records.

Prepared by: Evans, Mechwart, Hambleton & Tilton, Inc.


Registered Surveyor #6535

Description checked for
Mathematical Accuracy
ATHENS COUNTY
ENGINEER'S OFFICE

BY: 
DATE: 4-24-81