AUTHORITY	DATE INSTALLED OR RETIRED	DESCRIPTION
C-29,100 A.F.E. H506	Completed June 29, 1929.	Reconstruction of Bridge No. 145/10, station 7813+83.1.

CARBONDALE BR. JCT.

Note:
For Carbondale Branch
See Map No. 1, Vol. Sect. 31 OH 1482

ATHENS CO. OHIO
WATERLOO TWP.
T. 11 N., R. 15 W.

MINERAL O.
7830+308 = 0 Station

SCOTT STREET
HEWITT ST.
MAIN STREET
FRONT ST.

Wm. Shingler Sr.
RACCOON CREEK
Carbondale Coal Co.
Emmit Addis Est.
Mrs. M. Gickles
Hockey City
Channel Change
Lick Creek
1000 Market

D: 2°00'
1 = 35°58'

D: 2°00'
1 = 14°54'

D: 1°45'
1 = 24°16'

Note:
All chaining was done on the right hand rail and all distances out were measured from center-line of track.

Sheet No. 50 of 49 primary and 18 supplemental sheets of The Baltimore & Ohio Southwestern R.R. Co., V-145.1, Ohio Division, Main Line, from survey station 7814+40 to survey station 7867+20

A. M. Shaffer
Plat Engineer.

RECORD OF CHANGES AFTER DATE OF VALUATION

STATION MAP

THE BALTIMORE AND OHIO SOUTHWESTERN RAILROAD COMPANY
OPERATED BY
THE BALTIMORE AND OHIO RAILROAD COMPANY

OHIO DIVISION — MAIN LINE

STATION 7814+40 TO STATION 7867+20

SCALE: 1 IN. = 100 FT. JUNE 30, 1918

OFFICE OF VALUATION ENGINEER
BALTIMORE, MD.

Waterloo Sect. 27
Carbondale

REVISED TO		
1924	JUN	1925
1926	JUN	1926
1928	JUN	1928
1930	JUN	1930
1932	JUN	1932
1934	JUN	1934

V.145.1
S26

91-OH-145.1 (S-26)

R.S.C. 12-30-19