

SOUTHEASTERN LAND SURVEYS

LEONARD F. SWOYER
REGISTERED PROFESSIONAL LAND SURVEYOR

3428 Pleasant Hill Road Athens, Ohio 45701 740/593-8701

LOT 4

Situated in Lease Lot 1 of Section 25, Town 8, Range 14, Alexander Township, Athens County, Ohio and described as follows:

Commencing at a set iron at the approximate location of the Southeast corner of Lease Lot 1, said set iron pin is THE TRUE POINT OF BEGINNING; thence along the south line of said Lease Lot 1 and the north line of Lease Lot 4 and the south line of a 23.625 acre tract (the grantor's) described in Volume 332 Page 1294 of the Athens County Official Records and the north line of a 25.72 acre tract described in Volume 85 Page 518 of the Athens County Official Records on an assumed bearing North 80 degrees 21 minutes 18 seconds West, a distance of 730.00 feet to a found iron pin at the southeast corner of a 1.5 acre tract described in Volume 52 Page 522 of the Athens County Official Records; thence along the east line of said 1.5 acre tract North 6 degrees 54 minutes 18 seconds East, a distance of 255.57 feet to a found iron pin at the northeast corner of said 1.5 acre tract; thence along the north line of said 1.5 acre tract North 80 degrees 22 minutes 24 seconds West (passing a found iron pin at 236.32 feet) for a total distance of 255.94 feet to a point in the center of Alexander Township Road 41; thence along said road the following six courses and distances 1. North 3 degrees 51 minutes 44 seconds East, a distance of 31.15 feet to a point; thence 2. North 12 degrees 47 minutes 51 seconds East, a distance of 74.30 feet to a point; thence 3. North 20 degrees 49 minutes 47 seconds East, a distance of 59.00 feet to a point; thence 4. North 27 degrees 37 minutes 48 seconds East, a distance of 67.76 feet to a point; thence 5. North 35 degrees 10 minutes 05 seconds East, a distance of 48.99 feet to a point; thence 6. North 37 degrees 20 minutes 53 seconds East, a distance of 64.36 feet to a point; thence leaving said road South 50 degrees 36 minutes 34 seconds East (passing set iron pins at 25.60 feet, 77.38 feet and 952.12 feet) for a total distance of 1052.29 feet to a set iron pin on the east line of the grantor and the west line of a 40.33 acre tract described in Volume 300 Page 645 of the Athens County Official Records; thence along the east line of the grantor and the west line of the said 40.33 acre tract South 9 degrees 28 minutes 42 seconds West, a distance of 61.80 feet to the point of beginning and

> Description Checked for Mathematical Accuracy Athens County

> > CONSTRUCTION

SUBDIVISIONS

PROPERTY

ENGINEER'S OFFICE
BY: SISTANULL
DATE: 6-15-04

containing 6.1917 acres, and being a part of a 23.625 acre tract described in Volume 332 Page 1294 of the Athens County Official Records.

Note: Unless otherwise noted, all set iron pins are 5/8 inch diameter rebar and 30 inches in length and capped with a plastic identification marker inscribed L.F. Swoyer P.S. 6765.

The above description was prepared under the supervision of Leonard F. Swoyer Professional Land Surveyor Number 6765 and was based on a survey performed by Southeastern Land Surveys dated June 13, 2004. Subject to all easements and right of ways of record.

"Sight" Survey 970324-Z-0424 Tuesday, June 15, 2004 9:15 am. Pg: 1 Registered to: Athens County Engineers Department File Name: C:\OLDC\LOTSPL~1\ALEX\S25\T41-6-19.ZAK

P	Point Direction	Distance	Northing	Easting Eleva	ation		
Database opened: Tuesday, June 15, 2004 9:01 am.							
Assigned point							
	1		5000.00000	5000.00000	0.000		
Start	1		5000.00000	5000.00000	0.000		
Raw:	n80.2118w	730.00	3000.00000	3000.00000	0.000		
TR	N 80°21'18.0" W	730.000					
_	2	0.5.5.5.5	5122.30646	4280.31873	0.000		
Raw: TR	n06.5418e N 6°54'18.0'' E	255.57 255.570					
IIX	3	255.570	5376.02277	4311.04424	0.000		
Raw:	n80.2224w	255.94					
TR	N 80°22'24.0" W	255.940					
Raw:	4 n03.5144e	31.15	5418.82301	4058.70831	0.000		
TR	N 3°51'44.0" E	31.150					
	5		5449.90227	4060.80650	0.000		
Raw:	n12.4751e	74.30					
TR	N 12°47'51.0" E 6	74.300	5522.35658	4077.26439	0.000		
Raw:	n20.4947e	59.00	3322.33030	4077.20409	0.000		
TR	N 20°49'47.0" E	59.000					
-	7	07.70	5577.50042	4098.24431	0.000		
Raw: TR	n27.3748e N 27°37'48.0" E	67.76 67.760					
111	8	07.700	5637.53313	4129.66868	0.000		
Raw:	n35.1005e	48.99					
TR	N 35°10'05.0" E 9	48.990	5677.58080	4157.88578	0.000		
Raw:	n37.2053e	64.36	3077.30000	4137.00370	0.000		
TR	N 37°20'53.0" E	64.360					
	10	1050.00	5728.74474	4196.93012	0.000		
Raw: TR	s50.3634e S 50°36'34.0" E	1052.29 1052.290					
111	11	1002.290	5060.95821	5010.18002	0.000		
Raw:	s09.2842w	61.80					
TR	S 9°28'42.0" W	61.800	5000 00101	5000 00040	0.000		
	12		5000.00191	5000.00313	0.000		


"Sight" Survey 970324-Z-0424 Tuesday, June 15, 2004 9:15 am. Pg: 2

Registered to: Athens County Engineers Department File Name: C:\OLDC\LOTSPL~1\ALEX\S25\T41-6-19.ZAK

	Point Direction	Distance	Northing	Easting	Elevation
IN	S 58°32'59.6" W 1	0.004	5000.00000	5000.000	0.000

Area = 269712.737 Sq. Feet or 6.192 Acres

Database Saved: Tuesday, June 15, 2004 9:15 am.



Plat of SURVEY DF FOUR LOTS

Surveyed for: MARY F. WANDLING TRUST

Subdivision LEASE LOT 1

Township ALEXANDER

Corporation

County ATHENS

State OHIO

SUBJECT: DE DAY

SUBJECT

ALX#25